SITE IMPROVEMENT PLAN PROPOSED TRAILER STORAGE FACILITY

375 MAPLE AVENUE / ROUTE 163 TOWN OF MONTVILLE, CONNECTICUT 06382

PROPERTY

135 MAPLE AVENUE & ROUTE 163 MONTVILLE, CT MAP 031 BOOK 015 LOT 000 MAP 031 BOOK 019 LOT 000


ZONE

PROPERTY OWNER

349 MAPLE AVE., LLC 410 MAPLE AVENUE MONTVILLE, CT 06382

APPLICANT

349 MAPLE AVE., LLC 410 MAPLE AVENUE MONTVILLE, CT 06382



LOCATION & ZONING MAP

NTS

PREPARED FOR 349 MAPLE AVE. LLC 410 MAPLE AVENUE MONTVILLE CONNECTICUT 06382

Sheet List Table

Officer Elot Table				
Sheet Number	Sheet Title			
	Cover			
1	Advanced Survey LLC			
2	Existing Conditions Survey			
3	Test Pit Data			
4	Site Plan			
5	Grading & Drainage Plan			
6	E&S Plan			
7	E&S Notes & Details			
8	Construction Details			

(Revised January 13, 2025)

December 16, 2024

CLA Engineers, Inc.
CIVIL • STRUCTURAL • SURVEYING

317 Main Street Norwich, CT 06360
(860) 886-1966 Fax (860) 886-9165

GENERAL NOTES

- CONTRACTOR SHALL CONTACT "CALL BEFORE YOU DIG" AT 811 AT LEAST 2 FULL WORKING DAYS PRIOR TO THE START OF CONSTRUCTION.
 INFORMATION SHOWN ON THE DRAWINGS RELATING TO MATERIALS, CONDITIONS, AND/OR LOCATIONS OF EXISTING STRUCTURES AND UTILITIES HAS BEEN COMPILED FROM AVAILABLE INFORMATION INCLUDING FIELD SURVEY, UTILITY COMPANY AND TOWN RECORD MAPS AND
- DRAWINGS, AND IS NOT GUARANTEED ACCURATE OR COMPLETE.

 3. THE CONTRACTOR SHALL EXCAVATE TEST PITS AS NEEDED OR AS DIRECTED BY THE OWNER TO VERIFY UTILITY INFORMATION PRIOR TO TI START OF CONSTRUCTION.
- 4. MAINTENANCE AND PROTECTION OF TRAFFIC:

 A. THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ALL MAINTENANCE AND PROTECTION OF TRAFFIC, TRAFFIC CONTROL,

 TEMPORARY SIGNING OR BARRICADES, AND TEMPORARY LANE CLOSURES AS NEEDED. CONTINUOUS ACCESS FOR EMERGENCY VEHICLES
- SHALL BE MAINTAINED AT ALL TIMES.

 B. PASSAGE OF TRAFFIC ON ROADWAYS: A MINIMUM OF ONE LANE FOR TRAFFIC SHALL BE MAINTAINED AT ALL TIMES. THE CONTRACTOR
- SHALL PERFORM HIS OPERATIONS TO MINIMIZE DISRUPTIONS TO TRAFFIC WITHIN AND AROUND THE PROJECT SITE.


 C. RESIDENTS OR BUSINESSES WITH DRIVES AFFECTED BY CONSTRUCTION SHALL BE NOTIFIED BY THE CONTRACTOR AT LEAST 48 HOURS BEFORE CONSTRUCTION BEGINS AND SHALL BE ALLOWED CONTINUOUS ACCESS TO THEIR PROPERTY. IF WORK IS PERFORMED DURING THE SCHOOL YEAR, THE CONTRACTOR SHALL PROVIDE NOTICE TO THE BUS COMPANIES (PUBLIC & PRIVATE) AT LEAST 48 HOURS BEFORE CONSTRUCTION BEGINS. THE CONTRACTOR SHALL PHASE HIS CONSTRUCTION OPERATIONS AS NEEDED TO ALLOW CONTINUOUS
- D. TEMPORARY MODIFICATIONS TO TRAFFIC PATTERNS ON PUBLIC ROADWAYS SHALL CONFORM TO THE REQUIREMENTS OF CTDOT AND THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD)"
- E. CONSTRUCTION SIGNS MUST CONFORM TO THE SIGNING REQUIREMENTS OUTLINED IN THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD)". ALL SIGN FACES SHALL BE REFLECTORIZED.
- 5. THE CONTRACTOR SHALL CONFINE HIS OPERATIONS AND ACTIVITIES FOR CONSTRUCTION PURPOSES WITHIN THE STREET LINES, EASEMENTS AND PROPERTY AS SHOWN ON THE DRAWINGS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO EXISTING PAVEMENT, ROADWAY SIDEWALKS FTC. OUTSIDE OF THE WORK AREA AND SHALL REPAIR SUCH DAMAGE AT NO ADDITIONAL COST TO THE OWNER.
- 6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE TEMPORARY AND PERMANENT SUPPORT OF ALL EXISTING UTILITY POLES IN AN ADJACENT TO THE CONSTRUCTION AREA AND SHALL COMPLY WITH ALL THE REQUIREMENTS AND SPECIAL DETAILS FOR THE SUPPORT OF UTILITIES REQUIRED BY UTILITY AGENCIES. ALL COSTS FOR TEMPORARILY SUPPORTING UTILITY POLES DURING CONSTRUCTION SHALL BE INCLUDED IN OTHER ITEMS.
- 7. MATERIAL STOCKPILE AND STAGING AREAS: THE CONTRACTOR SHALL UTILIZE THE STOCKPILE, MATERIAL STORAGE AND EQUIPMENT STORAGE AREAS SHOWN ON THE PLANS. THE CONTRACTOR MAY ADJUST THE EXACT LOCATIONS IN THE FIELD AS NEED; IN NO CASE MAY THESE AREAS BE LOCATED CLOSER TO THE WETLANDS EDGE THAN SHOWN ON THE PLANS. PRIOR TO THE START OF CONSTRUCTION THE CONTRACTOR SHALL IDENTIFY THESE AREAS AND PROVIDE EROSION AND SEDIMENTATION CONTROL MEASURES AS REQUIRED.

 8. BLASTING MAY BE PERFORMED.
- 9. THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESETTING TO GRADE ALL FRAMES, GRATES, COVERS, VALVE BOXES, ACCESS COVERS, AND ALL OTHER ITEMS WHICH NORMALLY MUST HAVE A FIXED RELATION TO FINISHED GRADE.
- 10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION SURVEY AND STAKEOUT AS THEY NEED. CONTROL POINT INFO AND
- CAD FILES OF THE SITE PLAN CAN BE PROVIDED PRIOR TO CONSTRUCTION.

 11. ALL WORK TO CONFORM TO THE STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR ROADS,
- BRIDGES AND INCIDENTAL CONSTRUCTION FORM 818, DATED JANUARY 2024, AS REVISED.

 12. ANY DAMAGED AND/OR REMOVED PROPERTY CORNER (PINS & MONUMENTS) SHALL BE REPLACED BY A CONNECTICUT LICENSED LAND
- 13. A TOWN OF MONTVILLE PERMIT IS REQUIRED FOR WORK WITHIN THE TOWN ROW.

LEGEND TO DRAWINGS



APPROVED BY THE MONTVILLE PLANNING AND ZONING COMMISSION


FINAL APPROVAL:


CHAIRMAN SIGNATURE

DATE


DATE


EXPIRATION DATE:







EXISTING CONDITIONS SURVEY










EROSION & SEDIMENTATION CONTROL NARRATIVE

- THE EROSION & SEDIMENTATION CONTROL PLAN AND DETAILS HAVE BEEN DEVELOPED AS A STRATEGY TO CONTROL SOIL EROSION AND SEDIMENTATION DURING AND AFTER CONSTRUCTION. THIS PLAN IS BASED ON THE "2024 CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL" BY THE CONNECTICUT COUNCIL ON SOIL AND WATER CONSERVATION IN COOPERATION WITH THE CONNECTICUT DEEP.
- THE PROPOSED LOCATIONS OF SEDIMENT AND EROSION CONTROL MEASURES ARE SHOWN ON THE PLANS. THE CONTRACTOR SHALL PROVIDED SILT FENCE, STONE CHECK DAMS AND/OR OTHER EROSION CONTROL MEASURES AS NEEDED OR DIRECTED BY THE ENGINEER OR TOWN STAFF TO ADEQUATELY PREVENT SEDIMENT TRANSPORT.
- EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO SITE DISTURBANCE.
- TOWN STAFF SHALL BE NOTIFIED PRIOR TO THE START OF CONSTRUCTION TO INSPECT SEDIMENTATION AND EROSION CONTROL MEASURES
- THE CONTRACTOR SHALL INSPECT, REPAIR AND/OR REPLACE EROSION CONTROL MEASURES EVERY 7 DAYS AND IMMEDIATELY FOLLOWING ANY SIGNIFICANT RAINFALL OR SNOW MELT. SEDIMENT DEPOSITS MUST BE REMOVED WHEN WHEN DEPOSITS REACH APPROXIMATELY ONE HALF THE HEIGHT OF THE BARRIER. SEDIMENT CONTROL DEVICES SHALL REMAIN IN PLACE AND BE MAINTAINED BY THE CONTRACTOR UNTIL AREAS UPSLOPE ARE PERMANENTLY STABILIZED.
- STAKED HAY BALE SILT BARRIERS AND/OR SILT FENCE SHALL BE INSTALLED AROUND ANY TEMPORARY STOCKPILE AREAS. TEMPORARY VEGETATIVE COVER MAY BE REQUIRED (SEE
- INLET SEDIMENTATION CONTROL DEVICES SHALL BE INSTALLED UNDER THE GRATES OF ALL NEW CATCH BASINS AT THE TIME OF INSTALLATION, AND UNDER THE GRATES OF EXISTING CATCH BASINS IN THE CONSTRUCTION AREA.
- CONTINUOUS DUST CONTROL USING WATER OR APPROVED EQUAL SHALL BE PROVIDED FOR ALL EARTH STOCKPILES, EARTH PILED ALONG EXCAVATIONS, SURFACES OF BACKFILLED TRENCHES AND GRAVELED ROADWAY SURFACES. THE USE OF CALCIUM CHLORIDE FOR DUST CONTROL SHALL BE PROHIBITED.
- IF DEWATERING IS NECESSARY DURING ANY TIME OF CONSTRUCTION A CLEAR WATER DISCHARGE SHALL BE PROVIDED.
- 10. ALL DISTURBED AREAS SHALL BE RESTORED PER THE SLOPE STABILIZATION AND PERMANENT VEGETATION DETAILS. ALL DISTURBED AREAS THAT ARE SLOPED LESS THAN THREE HORIZONTAL TO ONE VERTICAL (3:1) SLOPE SHALL BE LOAMED, SEEDED, FERTILIZED AND MULCHED PER THE PERMANENT VEGETATIVE COVER SPECIFICATIONS. EROSION CONTROL MATTING OR STABILIZED HYDROSEED SHALL BE PROVIDED ON ALL DISTURBED AREAS THAT ARE SLOPED MORE THAN THREE HORIZONTAL TO ONE VERTICAL (3:1).
- 11. IF FINAL SEEDING OF DISTURBED AREAS IS NOT TO BE COMPLETED BEFORE OCTOBER 15, THE CONTRACTOR SHALL PROVIDE TEMPORARY MULCHING (DORMANT SEEDING MAY BE ATTEMPTED AS WELL) TO PROTECT THE SITE AND DELAY PERMANENT SEEDING.
- 12. WHEN FEASIBLE, TEMPORARY SEEDING OF DISTURBED AREAS THAT HAVE NOT BEEN FINISHED GRADED SHALL BE COMPLETED PRIOR TO OCTOBER 15.
- 13. ANY EROSION WHICH OCCURS WITHIN THE DISTURBED AREAS SHALL BE IMMEDIATELY REPAIRED AND STABILIZED. DURING THE CONSTRUCTION PHASE, INTERCEPTED SEDIMENT SHALL BE RETURNED TO THE SITE. POST SEEDING, INTERCEPTED SEDIMENT, IF ANY, SHALL BE DISPOSED OF IN A MANNER APPROVED BY THE TOWN AND ENGINEER.
- 14. EROSION AND SEDIMENTATION CONTROL MEASURES SHALL REMAIN IN PLACE UNTIL VEGETATION IS RE-ESTABLISHED OR SLOPES ARE STABILIZED AND REMOVAL IS APPROVED BY THE TOWN.
- 15. UNFORESEEN PROBLEMS WHICH ARE ENCOUNTERED IN THE FIELD SHALL BE SOLVED ACCORDING TO THE "2024 CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL" BY THE CONNECTICUT COUNCIL ON SOIL AND WATER CONSERVATION IN COOPERATION WITH THE CONNECTICUT DEEP.
- 16. THE OWNER'S REPRESENTATIVE SHALL BE RESPONSIBLE FOR THE EROSION AND SEDIMENTATION CONTROLS
 - WILLIAM P P&H CONSTRUCTION
 - Cell: 860-848-2372 bill@pandhconstruction.com



INSTALLATION NOTES:

1. PROVIDE 4" THICKNESS OF TOPSOIL OVER CLEAN FILL. PREPARE SOIL BEFORE INSTALLING BLANKETS, INCLUDING APPLICATION OF LIME FERTILIZER, AND SEED MIX PER PERMANENT VEGETATIVE COVER NOTES. (SHALL BE PAID

FOR AT THE UNIT PRICE FOR LOAM, SEED, FERTILIZE & MULCH)

BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE BLANKET IN 6" DEEP x 6" TRENCH, BACKFILL AND COMPACT THE TRENCH AFTER STAPLING ROLL THE BLANKET (A) DOWN OR (B) HORIZONTALLY ACROSS THE SLOPE. THE EDGES OF PARALLEL BLANKETS MUST BE STAPLED WITH APPROXIMATELY 2" OVERLAP. WHEN BLANKETS MUST BE SPLICED DOWN THE SLOPE, PLACE BLANKETS END OVER

PRODUCT NOTES:

1. EROSION CONTROL MATTING MUST BE LISTED ON THE LATEST CT DOT QUALIFIED PRODUCTS
LIST UNDER CLASS I: SLOPE PROTECTION, TYPE D.

END (SHINGLE STYLE) WITH APPROXIMATELY 4" OVERLAP. STAPLE THROUGH OVERLAPPED

EROSION CONTROL MATTING DETAIL (FOR 3:1 SLOPES OR STEEPER)

NOTES:

1. HYDROSEED SHALL BE INSTALLED IN ACCORDANCE WITH SECTION 9.50.3.6 OF DOT FORM 818. BONDED FIBER MATRIX (BFM) OR FLEXIBLE GROWTH MEDIUM (FGM) MUST BE INCLUDED IN THE HYDROSEED SLURRY. MIX RATE PERCENTAGES SHALL BE IN ACCORDANCE WITH THE MANUFACTURERS RECOMMENDATIONS FOR THE FINISHED SLOPES. THE FOLLOWING ARE ACCEPTABLE PRODUCTS:

PROFILE FLEXTERRA FGM PROFILE HYDRO-BLANKET BONDED FIBER MATRIX MAT, INC. SOIL GUARD BONDED FIBER MATRIX

NORTH AMERICAN GREEN HYDRA GT OR HYDRA CM THE REQUIRED SEED MIX SHALL BE IN ACCORDANCE WITH THE PERMANENT VEGETATIVE COVER NOTES. ALL APPLICATION RATES SHALL BE INCREASED BY 10% FOR HYDROSEEDING. THE CONTRACTOR SHALL ENSURE 100% COVERAGE OF THE DISTURBED SOIL.

HYDROSEED REQUIREMENTS (FOR 3:1 SLOPES OR STEEPER) 6" TOPSOIL PER PERMANENT VEGETATIVE -COVER NOTES UNDISTURBED AREA 4" CLEAN FILL

> TYPICAL LOAM & SEED SECTION DETAIL (FOR ALL DISTURBED AREAS)

SLOPE STABILIZATION DETAILS NOT TO SCALE

TEMPORARY VEGETATIVE COVER

A TEMPORARY SEEDING OF RYE GRASS WILL BE COMPLETED WITHIN 15 DAYS OF THE FORMATION OF STOCKPILES. IF THE SOIL IN THE STOCKPILES HAS BEEN COMPACTED BY CONSTRUCTION OPERATIONS IT SHALL BE LOOSENED TO A DEPTH OF 2 INCHES BEFORE THE FERTILIZER, LIME AND SEED IS APPLIED. 10-10-10 FERTILIZER AT A RATE OF 7.5 POUNDS PER 1000 S.F. LIMESTONE AT A RATE OF 90 LBS. PER 1000 S.F. SHALL BE USED. RYE GRASS APPLIED AT A RATE OF 1 LB. PER 1000 S.F. SHALL PROVIDE THE TEMPORARY VEGETATIVE COVER. STRAW FREE FROM WEEDS AND COARSE MATTER SHALL BE USED AT A RATE OF 70-90 LBS. PER 1000 S.F. AS A TEMPORARY MULCH. APPLY MULCH AND DRIVE TRACKED EQUIPMENT UP AND DOWN SLOPE OVER ENTIRE SURFACE SO CLEAT MARKS ARE PARALLEL TO THE CONTOURS.

PERMANENT VEGETATIVE COVER

TOPSOIL WILL BE REPLACED ONCE THE EXCAVATIONS HAVE BEEN COMPLETED AND THE SLOPES ARE GRADED AS SHOWN ON THE PLANS. PROVIDE SLOPE PROTECTION AS CALLED FOR ON THE PLANS AND DETAILS. TOPSOIL SHALL BE SPREAD AT A MINIMUM COMPACTED DEPTH OF 6 INCHES. ONCE THE TOPSOIL HAS BEEN SPREAD, ALL STONES TWO INCHES OR LARGER IN ANY DIMENSION WILL BE REMOVED AS WELL AS DEBRIS.

- APPLY AGRICULTURAL GROUND LIMESTONE AT THE RATE OF TWO TONS PER ACRE OR 100
- LBS. PER 1000 S.F. APPLY 10-10-10 FERTILIZER OR EQUIVALENT AT A RATE OF 300 LBS. PER ACRE OR
- 7.5 LBS. PER 1000 S.F. WORK LIMESTONE AND FERTILIZER INTO THE SOIL TO A DEPTH OF 4 INCHES
- INSPECT SEEDBED BEFORE SEEDING.
- IF TRAFFIC HAS COMPACTED THE SOIL, RETILL COMPACTED AREAS. APPLY THE FOLLOWING GRASS SEED MIX:

TYPICAL SEED MIXTURE

THE NEW ENGLAND ROADSIDE MATRIX UPLAND SEED MIX BY NEW ENGLAND WETLAND PLANTS, INC. APPLICATION RATE: 35 LBS/ACRE: 1,250 SF/LB. MIX IS DESIGNED FOR USE ALONG ROADS AND HIGHWAYS. THIS MIX CONTAINS NATIVE GRASSES, WILDFLOWERS, AND SHRUBS THAT ARE BLENDED TOGETHER AS A NATIVE MATRIX SEED MIX. IN AREAS THAT RECEIVE FREQUENT MOWING, THE COLD SEASON GRASSES WILL DOMINATE, SUCH AS THOSE AREAS CLOSEST TO THE ROADWAY SHOULDER. IN AREAS FARTHER TO THE ROAD, WHICH MAY BE MOWN ONLY ONCE EACH YEAR, OR IN HARD TO MOW AREAS, SUCH AS AROUND SIGNPOSTS, THE WILDFLOWER COMPONENT WILL BECOME DOMINANT. ALONG CUTS AND SIDE SLOPES WHICH MAY NEVER BE MOWN. THE SHRUB COMPONENT WILL ADD DIVERSITY AND BEAUTY TO THE ROADSIDE PLANTINGS. IT IS A PARTICULARLY APPROPRIATE SEED SIX FOR ROADSIDES, INDUSTRIAL SITES. OR CUT AND FILL SLOPES. THIS MIX MAY BE APPLIED BY HYDROSEEDING. OR BY MECHANICAL SPREADER. ALWAYS APPLY ON A CLEAN, WEED-FREE SEED BED. AFTER SOWING, LIGHTLY RAKE OR ROLL THE SITE TO IMPROVE SEED-TO-SOIL CONTACT. BEST RESULTS ARE OBTAINED WITH A

TYPICAL SEED MIXTURE FOR NON-MOWED SLOPES (3:1 OR STEEPER)

CT DEP SEED MIX NO. 26	LBS./ACRE	LBS./1000 S.F
SWITCHGRASS (BLACKWELL, SHELTER, CAVE-IN-ROCK)	4.0	0.10
BIG BLUESTEM (NIAGRA, KAW)	4.0	0.10
LITTLE BLUESTEM (BLAZE, ALDOUS, CAMPER)	2.0	0.05
SAND LOVEGRASS (NE-27, BEND)	1.5	0.03
BIRD'S-FOOT TREFOIL (EMPIRE VIKING)	2.0	0.05
	13.5	0.33

MID-LATE SPRING SEEDING. SUMMER SEEDING WILL BENEFIT FROM A LIGHT MULCHING OF CLEAN.

THE RECOMMENDED SEEDING DATES ARE: APRIL 1 - JUNE 15 AND AUGUST 15 - OCTOBER 15

WEED-FREE STRAW TO CONSERVE SOIL MOISTURE.

IMMEDIATELY FOLLOWING SEEDING, FIRM SEED BED WITH A ROLLER AND MULCH WITH WEED FREE STRAW. IF PERMANENT VEGETATIVE COVER IS HAS NOT BEEN ESTABLISHED BY OCTOBER 15, APPLY A TEMPORARY VEGETATIVE COVER ON THE TOPSOIL.

VEGETATIVE COVER FOR WATER QUALITY BASINS


SEED MIXTURE FOR SETTLING BASINS SHALL BE THE "NEW ENGLAND EROSION CONTROL/RESTORATION MIX FOR MOIST SITES" FROM NEW ENGLAND WETLAND PLANTS, AMHERST, MA, TELEPHONE NO. 413-548-8000

THE BEST RESULTS ARE OBTAINED WITH A SPRING SEEDING. SUMMER AND FALL SEEDING REQUIRE A LIGHT MULCHING OF WEED FREE STRAW TO CONSERVE MOISTURE. LATE FALL AND WINTER DORMANT SEEDING REQUIRE A 10% INCREASE IN THE SEEDING RATE. FERTILIZATION IS NOT REQUIRED UNLESS THE SOILS ARE PARTICULARLY INFERTILE

RAIN GARDEN SEED MIXTURE LBS./1000 S.F.

NEW ENGLAND EROSION CONTROL/RESTORATION MIX 0.80 FOR DETENTION BASINS AND MOIST SITES


SPECIES: Virginia Wild Rye, (Elymus virginicus), Creeping Red Fescue, (Festuca rubra), Little Bluestem, (Schizachyrium scoparium), Big Bluestem, (Andropogon gerardii), Fox Sedge, (Carex vulpinoidea), Switch Grass, (Panicum virgatum), Rough Bentgrass, (Agrostis scabra), New England Aster, (Aster novae—angliae), Boneset, (Eupatorium perfoliatum), Grass Leaved Goldenrod, (Euthamia graminifolia), Green Bulrush, (Scirpus atrovirens), Blue Vervain, (Verbena hastata), Soft Rush, (Juncus effusus), Wool Grass, (Scirpus cyperinus)



CONSTRUCTION NOTES:

- 1. SILT FENCE FILTER CLOTH TO BE SECURELY FASTENED TO GRADE STAKE
- WITH STAPLES, 6" ON CENTER. 2. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN ONE ANOTHER THEY SHALL
- OVERLAP BY 6" AND BE FOLDED. 3. BALES SHALL BE PLACED IN A ROW WITH ENDS TIGHTLY ABUTTING THE

SILT FENCE & HAYBALE DETAIL NOT TO SCALE



STORMWATER MANAGEMENT & POLLUTION PREVENTION PLAN

DURING CONSTRUCTION


- **POLLUTION PREVENTION TEAM:** THE CONTRACTOR SHALL BE RESPONSIBLE FOR CARRYING OUT THE PROVISIONS OF THIS PLAN.
- PARKING LOTS, SIDEWALKS AND OTHER IMPERVIOUS SURFACES BEYOND THE WORK SITE SHALL BE SWEPT CLEAN OF SAND, SILT AND LITTER DAILY AT THE END OF THE WORK DAY.
- **OUTSIDE STORAGE:** ACCESSORIES OR EQUIPMENT STORED OUTSIDE SHALL BE COVERED OR MAINTAINED TO MINIMIZE POSSIBILITY OF THESE MATERIALS OR THEIR RESIDUE PASSING TO STORM WATER.
- <u>WASHING:</u> NO WASHING OF VEHICLES, ACCESSORIES, EQUIPMENT, OR APPLIANCES IN WORK SITE.
- MAINTENANCE AND INSPECTION: A. THE CONTRACTOR SHALL INSPECT, REPAIR AND/OR REPLACE EROSION CONTROL MEASURES EVERY 7 DAYS AND IMMEDIATELY FOLLOWING ANY RAINFALL OF ½" OR MORE, OR SIGNIFICANT SNOW MELT. B. SEDIMENT DEPOSITS MUST BE REMOVED AND DISPOSED OF WHEN THEY REACH THE FOLLOWING LEVELS: SILT FENCE OR HAY BALES: ONE HALF THE HEIGHT OF THE SILT FENCE OR HAY BALE BARRIER.
 - INLET SEDIMENT CONTROL DEVICES (SILT SACKS): ONE HALF THE STORAGE VOLUME OF THE DEVICE OR WHEN THE RESTRAINT CORD IS NO LONGER VISIBLE.
- STONE CHECK DAMS AT INLETS: ONE HALF OF THE TEMPORARY SEDIMENT POOL HEIGHT. C. DAILY DUST CONTROL USING WATER OR APPROVED EQUAL SHALL BE PROVIDED FOR ALL EARTH STOCKPILES, EARTH PILED ALONG EXCAVATIONS, SURFACES OF BACKFILLED TRENCHES AND GRAVELED
- SURFACES. D. SILT FENCE AND INLET SEDIMENT CONTROL DEVICES SHALL BE REPLACED WITH RIPS OR DETERIORATION IN THE GEOTEXTILE FABRIC ARE FOUND ON INSPECTION. HAY BALES SHALL BE REPLACED IF THEY HAVE DETERIORATED OR DECOMPOSED TO THE POINT WHERE THEY HAVE LOST STRUCTURAL INTEGRITY. CRUSHED STONE SHALL BE REMOVED AND REPLACED IF SILT HAS ACCUMULATED WITH THE STONE
- VOIDS TO PREVENT THE PASSAGE OF WATER THROUGH THE STONE. SPILLS OR ACCIDENTAL DISCHARGES:
- A. COMPLY WITH STATE AND FEDERAL REGULATIONS TO CONTAIN AND CLEAN UP ANY SPILL OR DISCHARGE AND DISPOSE OF MATERIALS AT AN APPROVED FACILITY.
- B. CONTACT CONNECTICUT DEEP OIL AND CHEMICAL SPILL RESPONSE DIVISION (860) 424-3338 C. THE FOLLOWING STEPS SHOULD BE PERFORMED AS SOON AS POSSIBLE:
- STOP THE SOURCE OF THE SPILL
- CONTAIN THE SPILL
- COVER SPILL WITH ABSORBENT MATERIAL SUCH AS KITTY LITER, SAWDUST OR OIL ABSORBENT PADS. DO NOT USE STRAW. • DISPOSE OF ABSORBER IN ACCORDANCE WITH LOCAL AND STATE REGULATIONS.


POST CONSTRUCTION

- **POLLUTION PREVENTION TEAM:** THE OWNERS SHALL BE RESPONSIBLE FOR CARRYING OUT THE PROVISIONS OF THIS PLAN.
- SWEEPING: PARKING LOTS, SIDEWALKS AND OTHER IMPERVIOUS SURFACES SHALL BE SWEPT CLEAN OF SAND AND LITTER AND ANY OTHER POLLUTANTS AT LEAST TWICE PER YEAR.
- A. BETWEEN NOVEMBER 15 AND DECEMBER 15 (AFTER LEAF FALL)
- - ACCESSORIES OR EQUIPMENT STORED OUTSIDE SHALL BE COVERED OR MAINTAINED TO MINIMIZE POSSIBILITY OF THESE MATERIALS OR THEIR RESIDUE PASSING TO STORM WATER.
- <u>WASHING:</u> NO WASHING OF VEHICLES, ACCESSORIES, EQUIPMENT OR APPLIANCES IN PARKING AREAS.
- MAINTENANCE AND INSPECTION: SEE OPERATIONS AND MAINTENANCE SCHEDULE


B. DURING APRIL (AFTER SNOW MELT)


- SPILLS OR ACCIDENTAL DISCHARGES: A. COMPLY WITH STATE AND FEDERAL REGULATIONS TO CONTAIN AND CLEAN UP ANY SPILL OR DISCHARGE AND DISPOSE OF MATERIALS AT AN APPROVED FACILITY.
- B. CONTACT CONNECTICUT DEEP OIL AND CHEMICAL SPILL RESPONSE DIVISION (860) 424-3338
- C. THE FOLLOWING STEPS SHOULD BE PERFORMED AS SOON AS POSSIBLE: STOP THE SOURCE OF THE SPILL
 - CONTAIN THE SPILL
 - COVER SPILL WITH ABSORBENT MATERIAL SUCH AS KITTY LITER, SAWDUST OR OIL ABSORBENT PADS. DO NOT USE STRAW. DISPOSE OF ABSORBER IN ACCORDANCE WITH LOCAL AND STATE REGULATIONS.





NOT TO SCALE








Maintenance Schedule for Stormy	
Activity	Schedule
Prior to new spring growth reaching a height of 2" (e.g., shortly after forsythia or redbud blooms), trim any material standing from the previous year close to the ground (approximately 2").	
This will allow the soil to warm more quickly, which will stimulate the emergence and	
growth of native seedlings and reduce the likelihood of the meadow being invaded by	
shrubs.	
Problem weeds should be hand pulled or spot sprayed with an approved herbicide, such as Rodeo® or Garlon® 3A.	
If you did not plant vines or spiny plants as part of your mix, be vigilant about controlling	Second growing season
them. These are more easily pulled when they are young rather than after they have had	
two to three months of growth. Examples include bindweed, blackberry, multiflora rose,	
mile-a-minute and Japanese hops. Be equally vigilant about controlling other invasive	
species, such as autumn olive and Japanese knotweed.	
Special Circumstances	
If you notice a heavy infestation of ragweed or foxtail in the second growing season, trim the	
meadow to a height of 8". Trimming should cease by mid-September.	
For the basin and side slopes, inspect for invasive vegetation.	
Grassy weeds or persistent perennials can re-establish in these soils. Monitor and control weeds by	Monthly
hand pulling or spot spraying.	
nspect for damage, undercut, or eroded area	
nspect Sediment Forebay and monitor for sediment accumulation. Remove any trash and organic	
lebris (leaves) in spring & fall. Remove sediment from the sediment forebay or other pretreatment area	
when it accumulates to a depth of more than 12 inches or 50% of the design depth. Clean outlet of	
sediment forebay or other pretreatment measures when drawdown time exceeds 36 hours after the end of a storm event.	
Remove sediment from the infiltration basin surface when the sediment accumulation exceeds 2 inches	
or when drawdown time exceeds 48 hours after the end of a storm event, indicating that the system is	Semi-Annually
clogged.	
Weed as necessary. Mow grass within infiltration basin to a height of 3 to 6 inches. Maintain a healthy,	
vigorous stand of grass cover; re-seed as necessary.	
Clean and remove debris & sediment from inlet and outlet structures.	
Mow side slopes. Close mowing throughout the regular growing season or extensive chemical use is	
not conducive to water quality improvement and wildlife habitat. Spring mowed vegetation can typically	
remain within basins providing cover for new emerging vegetation.	
Repair undercut or eroded areas.	As needed maintenance


Maintenance Schedule for Trailer Storage Areas				
Activity	Schedule			
Sweep parking lots & impervious areas	 Between November 15th and December 15th (after leaf fall) During April (after snow melt) 			
Remove and dispose of trash and debris onsite	Daily - As needed maintenance			
Maintenance Schedul	le for Qualifying Pervious Area (QPA)			
Activity	Schedule			

Maintenance Schedule for Qualifying Pervious Area (QPA)					
Activity	Schedule				
Sweep impervious areas	 Between November 15th and December 15th (after leaf fall) During April (after snow melt) 				
Inspect QPA for erosion and loss of vegetation	Annually - As needed maintenance				
Remove and dispose of trash and debris onsite	Annually - As needed maintenance				











1. CONTRACTOR SHALL PROTECT EXCAVATIONS BY SHORING, BRACING, SHEET PILING, UNDERPINNING OR OTHER METHODS TO PREVENT CAVE—IN OR LOOSE SOIL FROM FALLING INTO THE EXCAVATION AND DAMAGING THE WORK OR ADJACENT STRUCTURES AND UTILITIES.





PROVIDE CONTINUOUS TACK COAT ALONG EDGE WHEN MATCHING EXISTING PAVEMENT CONTRACTOR TO PROVIDE COMPACTION ON ALL TRENCH BACKFILLS, EXCAVATIONS AND PAVEMENT BASES TO NOT LESS THAN 95% OF THE DRY DENSITY FOR THAT MATERIAL WHEN TESTED IN ACCORDANCE WITH AASHTO T180, METHOD D TYPICAL PAVEMENT SECTION DETAIL NOT TO SCALE




BITUMINOUS CONCRETE LIP CURBING


NOT TO SCALE







TYPE A - RIPRAP APRON NOT TO SCALE



60-80% 5% DO NOT COMPACT MATERIAL DURING INSTALLATION. 2. FINE SAND SHALL MEET THE FOLLOWING GRADATION: Sieve % Passing No, 20 100% 100 % 100 %

3. EXCAVATE WATER QUALITY BASIN TO THE GRADES SPECIFIED WITH SIDEWALLS AS NEAR TO VERTICAL AS POSSIBLE. INSTALL PERVIOUS TOPSOIL MIX. DO NOT COMPACT TOPSOIL MIX.

4. SEED MIX SHALL CONFORM THE REQUIREMENTS SPECIFIED IN THE VEGETATIVE COVER NARRATIVE HEREIN. INSTALL SHRUBS AND ALL PLANTINGS IN CONFORMANCE WITH THE CONSTRUCTION DETAILS AND LANDSCAPING NOTES HEREIN.

6" TOPSOIL & SEED (MIN.)

EMBANKMENT FILL MATERIAL SHALL CONSIST OF THE FOLLOWING

A. CLEAN MINERAL SOIL, FREE OF ROOTS, WOODY VEGETATION, STUMPS, SOD, OVERSIZED STONES, ROCKS, OR OTHER ORGANIC UNSUITABLE MATERIAL.

B. SHALL BE A NON-FREE DRAINING GLACIAL TILL

C. MATERIAL SHALL CONTAIN AT LEAST 15% PASSING THE #200 SIEVE AND NOT MORE THAN 50%

D. NO STONES LÄRGER THAN 6" SHALL BE ALLOWED WITHIN THE EMBANKMENT.

FINAL APPROVAL:

DATE OF APPROVAL:

EXPIRATION DATE:

OF EACH LIFT SHALL BE SCARIFIED PRIOR TO THE PLACEMENT OF THE NEXT LIFT.

EMBANKMENT FILL SHALL BE COMPACTED TO 90%-95% STANDARD PROCTOR COMPACTION

E. NO STONES LARGER THAN 3" SHALL BE ALLOWED WITHIN 2 FEET OF STRUCTURES. EMBANKMENT FILL SHALL BE PLACED IN MAXIMUM 9" LIFTS. THE EXISTING GRADE AND THE SURFACE

STORMWATER QUALITY BASIN EMBANKMENT FILL SECTION DETAIL

2:1 SLOPE MAX.

- EXISTING GRADE

EMBANKMENT FILL MATERIAL

(SEE NOTES)

APPROVED BY THE LISBON PLANNING AND ZONING COMMISSION

CHAIRMAN SIGNATURE

DATE

(SEE PLANS FOR GRADING)

MAINTENANCE:

1. MOW BOTTOM 2-3 TIMES PER YEARS, AS NEEDED. REPLENISH MULCH AROUND PLANTINGS AS NEEDED. REMOVE SEDIMENT AND LEAF LITTER TWICE YEARLY A. BETWEEN NOVEMBER 15 AND DECEMBER 15 (AFTER LEAF FALL) B. DURING APRIL (AFTER SNOW MELT)

No. 100 50-75 %


TYPICAL STORMWATER QUALITY BASIN DETAILS

100-YR_STORM ▽

CLEAR, GRUB & STRIP

PASSING THE #200 SIEVE.

TOPSOIL BELOW EMBANKMENT FILL




WIDTH = 2' → GRASSED WATERWAY

GRASS LINED SWALE DETAIL

GRADE TO PROVIDE SMOOTH

SHOP TWISTED RAIL

TRANSITION (TYP. BOTH SIDES)



STABILIZE SWALE WITH EROSION CONTROL MATTING TYPE F PER CTDOT APPROVED MATERIALS LIST


PROVIDE LOAM & SEED
- PER PERMANENT VEGETATIVE

EXISTING SUBGRADE

OR GRAVEL FILL

COVER DETAILS (6" MIN.)





INSTALLATION OF RAIL AND ANCHORAGES TO BE IN ACCORDANCE WITH THE REQUIREMENTS OF CT DOT. METAL BEAM RAIL TO BE DOT TYPE RB-350 PER DOT SPECIFICATIONS. PROVIDE RB-TYPE II END ANCHORAGES PER DOT SPECIFICATIONS.

METAL BEAM RAIL AND END ANCHORAGE

