

SITE IMPROVEMENT PLAN

PROPOSED TRAILER STORAGE FACILITY

375 MAPLE AVENUE / ROUTE 163
TOWN OF MONTVILLE, CONNECTICUT

PROPERTY
375 MAPLE AVENUE (031-015-000)
ROUTE 163 (031-019-000)

ZONE
INDUSTRIAL

PROPERTY OWNER
RAND-WHITNEY REALTY, LLC
ONE AGRAND ST,
WORCESTER, MA 01607

APPLICANT
RAND-WHITNEY REALTY, LLC
ONE AGRAND ST,
WORCESTER, MA 01607

PREPARED FOR
RAND-WHITNEY REALTY, LLC
ONE AGRAND ST,
WORCESTER, MA 01607

- GENERAL NOTES**
- CONTRACTOR SHALL CONTACT "CALL BEFORE YOU DIG" AT 811 AT LEAST 2 FULL WORKING DAYS PRIOR TO THE START OF CONSTRUCTION.
 - INFORMATION SHOWN ON THE DRAWINGS RELATING TO MATERIALS, CONDITIONS, AND/OR LOCATIONS OF EXISTING STRUCTURES AND UTILITIES HAS BEEN COMPILED FROM AVAILABLE INFORMATION INCLUDING FIELD SURVEY, UTILITY COMPANY AND TOWN RECORD MAPS AND DRAWINGS, AND IS NOT GUARANTEED ACCURATE OR COMPLETE.
 - THE CONTRACTOR SHALL EXCAVATE TEST PITS AS NEEDED OR AS DIRECTED BY THE OWNER TO VERIFY UTILITY INFORMATION PRIOR TO THE START OF CONSTRUCTION.
 - MAINTENANCE AND PROTECTION OF TRAFFIC:**
 - THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR ALL MAINTENANCE AND PROTECTION OF TRAFFIC, TRAFFIC CONTROL, TEMPORARY SIGNING OR BARRICADES, AND TEMPORARY LANE CLOSURES AS NEEDED. CONTINUOUS ACCESS FOR EMERGENCY VEHICLES SHALL BE MAINTAINED AT ALL TIMES.
 - PASSAGE OF TRAFFIC ON ROADWAYS: A MINIMUM OF ONE LANE FOR TRAFFIC SHALL BE MAINTAINED AT ALL TIMES. THE CONTRACTOR SHALL PERFORM HIS OPERATIONS TO MINIMIZE DISRUPTIONS TO TRAFFIC WITHIN AND AROUND THE PROJECT SITE.
 - RESIDENTS OR BUSINESSES WITH DRIVES AFFECTED BY CONSTRUCTION SHALL BE NOTIFIED BY THE CONTRACTOR AT LEAST 48 HOURS BEFORE CONSTRUCTION BEGINS AND SHALL BE ALLOWED CONTINUOUS ACCESS TO THEIR PROPERTY. IF WORK IS PERFORMED DURING THE SCHOOL YEAR, THE CONTRACTOR SHALL PROVIDE NOTICE TO THE BUS COMPANIES (PUBLIC & PRIVATE) AT LEAST 48 HOURS BEFORE CONSTRUCTION BEGINS. THE CONTRACTOR SHALL PHASE HIS CONSTRUCTION OPERATIONS AS NEEDED TO ALLOW CONTINUOUS ACCESS TO ALL BUSINESSES WITHIN THE PROJECT AREA.
 - TEMPORARY MODIFICATIONS TO TRAFFIC PATTERNS ON PUBLIC ROADWAYS SHALL CONFORM TO THE REQUIREMENTS OF CTDOT AND THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD)".
 - CONSTRUCTION SIGNS MUST CONFORM TO THE SIGNING REQUIREMENTS OUTLINED IN THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD)". ALL SIGN FACES SHALL BE REFLECTORIZED.
 - THE CONTRACTOR SHALL CONFINE HIS OPERATIONS AND ACTIVITIES FOR CONSTRUCTION PURPOSES WITHIN THE STREET LINES, EASEMENTS AND PROPERTY AS SHOWN ON THE DRAWINGS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO EXISTING PAVEMENT, ROADWAY, SIDEWALKS, ETC., OUTSIDE OF THE WORK AREA AND SHALL REPAIR SUCH DAMAGE AT NO ADDITIONAL COST TO THE OWNER.
 - THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE TEMPORARY AND PERMANENT SUPPORT OF ALL EXISTING UTILITY POLES IN AN ADJACENT TO THE CONSTRUCTION AREA AND SHALL COMPLY WITH ALL THE REQUIREMENTS AND SPECIAL DETAILS FOR THE SUPPORT OF UTILITIES REQUIRED BY UTILITY AGENCIES. ALL COSTS FOR TEMPORARILY SUPPORTING UTILITY POLES DURING CONSTRUCTION SHALL BE INCLUDED IN OTHER ITEMS.
 - MATERIAL STOCKPILE AND STAGING AREAS: THE CONTRACTOR SHALL UTILIZE THE STOCKPILE, MATERIAL STORAGE AND EQUIPMENT STORAGE AREAS SHOWN ON THE PLANS. THE CONTRACTOR MAY ADJUST THE EXACT LOCATIONS IN THE FIELD AS NEEDED; IN NO CASE MAY THESE AREAS BE LOCATED CLOSER TO THE WETLANDS EDGE THAN SHOWN ON THE PLANS. PRIOR TO THE START OF CONSTRUCTION THE CONTRACTOR SHALL IDENTIFY THESE AREAS AND PROVIDE EROSION AND SEDIMENTATION CONTROL MEASURES AS REQUIRED.
 - BLASTING MAY BE PERFORMED.
 - THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESETTLE TO GRADE ALL FRAMES, GRATES, COVERS, VALVE BOXES, ACCESS COVERS, AND ALL OTHER ITEMS WHICH NORMALLY MUST HAVE A FIXED RELATION TO FINISHED GRADE.
 - THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION SURVEY AND STAKEOUT AS THEY NEED. CONTROL POINT INFO AND CAD FILES OF THE SITE PLAN CAN BE PROVIDED PRIOR TO CONSTRUCTION.
 - ALL WORK TO CONFORM TO THE STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR ROADS, BRIDGES AND INCIDENTAL CONSTRUCTION FORM 818, DATED JANUARY 2024, AS REVISED.
 - ANY DAMAGED AND/OR REMOVED PROPERTY CORNER (PINS & MONUMENTS) SHALL BE REPLACED BY A CONNECTICUT LICENSED LAND SURVEYOR.
 - A TOWN OF MONTVILLE PERMIT IS REQUIRED FOR WORK WITHIN THE TOWN ROW.



LOCATION & ZONING MAP
NTS

Sheet List Table	
Sheet Number	Sheet Title
0	Cover
1	Advanced Survey
2	Existing Conditions
3	Test Pit Data
4	Site Plan
5	Grading & Drainage Plan
6	E&S Plan
7	E&S Notes & Details
8	Construction Details

LEGEND TO DRAWINGS

EXISTING		PROPOSED
---	PROPERTY LINE	---
---	BUILDING SETBACK LINE	---
---	CATCH BASIN & CULVERT	---
W	WATER	W
S	SEWER	S
FM	SEWER FORCE MAIN	FM
G	GAS	G
126	CONTOUR	126
124.2 (ex.) x	SPOT ELEVATION	124.2 (PR.) x
Ø	UTILITY POLE	Ø
E	ELECTRIC	E
T	TELEPHONE	T
ET	ELECTRIC & TELECOM.	ET
SF	SILT FENCE	SF
F	FENCE	F
---	RETAINING WALL	---
---	STONE WALL	---
+	TEST HOLE	+
---	TREE/SHRUB LINE	---

June 2, 2025

CLA Engineers, Inc.
CIVIL • STRUCTURAL • SURVEYING
317 Main Street Norwich, CT 06360
(860) 886-1966 Fax (860) 886-9165

APPROVED BY THE MONTVILLE PLANNING AND ZONING COMMISSION

FINAL APPROVAL: _____

CHAIRMAN SIGNATURE _____ DATE _____

DATE OF APPROVAL: _____


EXPIRATION DATE: _____

NOTES:

1. THIS SURVEY HAS BEEN PREPARED PURSUANT TO THE REGULATIONS OF CONNECTICUT STATE AGENCIES SECTIONS 20-300b-1 THROUGH 20-300b-20 AND THE "STANDARDS FOR SURVEYS AND MAPS IN THE STATE OF CONNECTICUT" AS ADOPTED BY THE CONNECTICUT ASSOCIATION OF LAND SURVEYORS, INC. ON SEPTEMBER 26, 1996. IT IS A PROPERTY SURVEY BASED ON A RESURVEY AND CONFORMS TO HORIZONTAL ACCURACY CLASS A-2.
2. FOR SUBJECT PROPERTY REFERENCE IS MADE TO THE TOWN OF MONTVILLE LAND RECORDS VOLUME 679 - PAGE 003 & VOLUME 690 - PAGE 912.
3. THE PROPERTY IS SUBJECT TO A SEWER LINE EASEMENT AS RECORDED IN THE MONTVILLE LAND RECORDS VOLUME 121 - PAGE 79.
4. THE PROPERTIES ARE LOCATED IN ZONING DISTRICT - INDUSTRIAL.
5. THE LIMITS OF THE INLAND WETLANDS WERE DELINEATED BY JOSEPH R. THEROUX ON 11/27/23.


MAP REFERENCES:

1. MAP SHOWING LAND DIVISION FOR ALBERT & JUNE POST, MAPLE AVENUE, MONTVILLE, CONNECTICUT, SCALE: 1"=20', DATE: OCT. 15, 1975, PREPARED BY RAMON S. MAGSOMBOL, L.S.



LEGEND:

VOL.	VOLUME
PG.	PAGE
N/F	NOW OR FORMERLY
S.F.	SQUARE FEET
IP	IRON PIPE
MON	MONUMENT
IPIN	IRON PIN
REC.	RECOVERED
DH	SET
SMH	SANITARY MANHOLE
CB	CATCH BASIN
CL&P	CONNECTICUT LIGHT & POWER
CONC.	CONCRETE




TO MY KNOWLEDGE AND BELIEF, THIS MAP IS SUBSTANTIALLY CORRECT AS NOTED HEREON. THIS MAP IS NOT VALID WITHOUT A LIVE SIGNATURE AND THE EMBOSSED SEAL OF THE SURVEYOR HEREON.

RICHARD A. DESCHAMPS L.S. #70019 4/30/25 DATE



PROJECT NO.	23-088	PROPERTY SURVEY PREPARED FOR 349 MAPLE AVENUE, LLC #349 & #375 MAPLE AVENUE MONTVILLE, CONNECTICUT
DRAWN BY:	R.A.D.	
DATE:	8/24/23	
SCALE:	1"=30'	
SHEET	1 OF 1	
REVISIONS		
12/1/23	WETLAND LIMITS ADDED	
3/18/24	TOPOGRAPHY ADDED	
5/29/24	WOOD CHIP AREAS BORING STK LOCATIONS	
6/2/24	TOPO & LOCATIONS	
GRAPHIC SCALE IN FEET		ADVANCED SURVEYS, LLC. 60 Terry Road, Griswold, CT 06351 Phone (860)639-8928

LEGEND:

- PROPERTY LINE
- CHAIN-LINK FENCE
- RETAINING WALL
- WETLANDS EDGE
- STONE WALL
- BOUNDARY POINT
- IRON PIN, IRON PIPE
- CHD, MON
- MONUMENT
- GAS GATE, WATER GATE
- TRAFFIC SIGN
- SEWER MANHOLE
- FLOOD ZONE AE (FROM FIRM PANEL 09011C0334G 7/18/2011)
- REGULATORY FLOODWAY
- UPLAND REVIEW AREA
- UTILITY POLE
- NOW OR FORMERLY UNDER GROUND
- DECIDUOUS TREE
- OVERHEAD ELECTRIC LINE
- WATER SHUTOFF
- BOLLARD
- SHRUB
- WETLANDS VEGETATION, FLAG



LOCATION MAP
(NOT TO SCALE)



SURVEY NOTES

- THIS SURVEY AND MAP HAS BEEN PREPARED IN ACCORDANCE WITH SECTION 20-300b-1 THRU 20-300b-20 OF THE REGULATIONS FOR STATE AGENCIES "STANDARDS FOR SURVEYS AND MAPS IN THE STATE OF CONNECTICUT" AS ENDORSED BY THE CONNECTICUT ASSOCIATION OF LAND SURVEYORS, INC.
 - TYPE OF SURVEY: TOPOGRAPHIC SURVEY
 - HORIZONTAL ACCURACY: A-2
 - VERTICAL ACCURACY: V-2
 - TOPOGRAPHIC ACCURACY: T-2
 - INTENT: TO DEPICT EXISTING CONDITIONS OF THE SUBJECT PARCEL.
- DATE OF LATEST FIELD WORK: NOVEMBER 2024
- HORIZONTAL ORIENTATION IS CT N.A.D. 83 BASED ON FIELD GPS OBSERVATIONS
- VERTICAL DATUM IS N.A.V.D. 88 BASED ON FIELD GPS OBSERVATIONS.
- THE WORD "CERTIFY" IS UNDERSTOOD TO BE AN EXPRESSION OF THE PROFESSIONAL OPINION OF THE LAND SURVEYOR TO THE BEST OF THEIR KNOWLEDGE, INFORMATION AND BELIEF.
- THIS PLAN COMBINES BOUNDARY AND LOCATION DATA FROM SHEET 1 WITH ADDITIONAL FIELD LOCATIONS CONDUCTED BY CLA ENGINEERS, AS LABELED.
- CONTOUR DATA DEPICTED IS A MIXTURE OF 2016 LIDAR DATA (OUTSIDE LIMITS) AND LOCAL FIELD OBSERVATIONS NAVD88 RECORDED BY CLA (INSIDE LIMITS).
- FOR MORE DETAILED BOUNDARY DATA AND INFORMATION SEE SHEET 1.
- A PRINT OR MYLAR OF THIS MAP IS NOT VALID UNLESS IT CONTAINS THE SEAL AND LIVE SIGNATURE OF THE SURVEYOR.

I HAVE REVIEWED THE WETLANDS ON THE PROPERTY IN THE FIELD AND HAVE REVIEWED THE WETLANDS AS SHOWN ON THE PLAN AND FIND THAT THEY SUBSTANTIALLY REPRESENT THE WETLANDS AS DELINEATED IN THE FIELD.

RC Russo
ROBERT C. RUSSO
CERTIFIED SOIL SCIENTIST

APPROVED BY THE MONTVILLE PLANNING AND ZONING COMMISSION


FINAL APPROVAL: _____ DATE _____

DATE OF APPROVAL: _____

EXPIRATION DATE: _____

TO MY KNOWLEDGE AND BELIEF THIS PLAN IS SUBSTANTIALLY CORRECT AS NOTED OR DEPICTED HEREON.

RYAN J. CHEVERIE, L.L.S. #70454



CLA Engineers, Inc. CIVIL • STRUCTURAL • SURVEYING 317 Main Street Norwich, CT 06360 (860) 886-1966 Fax (860) 886-9165		Project No. CLA-7767F Proj. Surveyor R.J.C. Date: DEC. 2024 Sheet No. 2
TOWN OF MONTVILLE, CT, 06353 PREPARED FOR RAND-WHITNEY REALTY, LLC EXISTING CONDITIONS		

TEST PIT DATA

TEST PITS EXCAVATED BY P&H CONSTRUCTION
AS WITNESSED BY CLA ENGINEERS (D. Hayward & B. Russo)
07/18/2024.

TP-1
Total Depth = 50"
0' - 15" Topsoil: Very dark brown, organic loam
15" - 46" Subsoil: Light gray brown loamy sand
46" - 50" Brown sand and gravel
Groundwater @ 39" (Elev.=230.3)
No ledge
Mottles @ 30" (Elev.=231.0)

TP-2
Total Depth = 87"
0' - 35" Wood chips
35" - 45" Topsoil:
45" - 73" Subsoil: Light brown-gray-green silt
73" - 83" Yellow brown fine sandy loam
83" - 87" Brown sand and gravel with pebbles
and cobbles with trace silt
Groundwater at 76" (Elev.=230.9)
No ledge
No Mottles

TP-3 (Sample taken from 25" - 73")
Total Depth = 73"
0" to 7" Topsoil: Brown fine sandy loam
7" to 25" Subsoil: Yellow brown fine sandy loam with cobbles and stones
25" to 73" Light brown, medium to coarse sand with gravel, cobbles and stones.
Firm in place.
No Groundwater
No mottles
No Ledge

TP-4
Total Depth = 51"
0" to 13" Topsoil: Dark brown silty loam
13" to 26" Subsoil: Light brown silty loam
26" to 35" Dark yellow brown sand and gravel with trace silt
35" to 51" Yellow brown coarse sand and gravel
No Groundwater
No Ledge
Mottles @ 22" (Elev. 235.3)


TP-5 - Not performed

TP-6 (Sample taken from 8" - 22")
Total Depth = 66" (Firm at bottom)
0" - 8" Topsoil: Brown silty loam
8" - 22" Subsoil: Yellow brown fine sandy loam with gravel
22" - 42" Yellow brown coarse sand and gravel with cobbles
Firm in place. Manganese staining.
42" to 66" Light brown medium sand and gravel and stones.
Groundwater @ 63" (Elev.=230.57)
No ledge
Mottles @ 33" (Elev.=233.07)

TP-7
Total Depth = 85"
0" - 9" Topsoil: Dark brown sandy loam
9" - 21" Subsoil: Brown fine sandy loam
21" - 85" Light brown sand and gravel with cobbles and stones
(46" Manganese staining - Dense)
No Groundwater
No ledge
No Mottles

TP-8 (Sample taken at 46" - 60")
Total Depth = 86"
0" - 16" Topsoil: Fill. Dark brown, light brown loamy sand
16" - 26" Original topsoil: Dark brown silty loam
26" - 46" Yellow brown sandy loam with cobbles and stones
46" - 60" Strong brown, light brown very fine sand
60" - 86" Gray, light brown sand and gravel with cobbles and stone
No Groundwater
No ledge
Mottles at 36" (Elev.=235.17)

TP-9 (Sample taken from 16" to 45")
Total Depth = 62"
0" - 16" Topsoil: Very dark brown, fine sandy loam
16" - 45" Subsoil: Yellow brown fine sandy loam with cobbles and stones
45" - 62" Gray brown coarse sand and gravel with cobbles
Groundwater at 45" (Elev.=229.4)
No ledge
Mottles at 28" (Elev.=230.8)



LEGEND

NRCS SOIL BOUNDARY

SOIL SYMBOL (HYDROLOGICAL GROUP)
SOIL DESCRIPTION

UPLAND REVIEW AREA

40' 0 40' 80'
SCALE: 1"=40'

No.	DATE	REVISION



CLA Engineers, Inc.
Civil • Structural • Surveying
317 Main Street Norwich, CT 06360
(860) 886-1966 Fax (860) 886-9165


RAND-WHITNEY REALTY, LLC

PROPOSED TRAILER STORAGE
375 MAPLE AVENUE & ROUTE 163
MONTVILLE, CT

TEST PIT DATA

Project No.
CLA-7767F
Proj. Engineer
D.P.H.
Date:
06/02/25
Sheet No.

3



ZONING COMPLIANCE CHART
(375 MAPLE AVE)
INDUSTRIAL DISTRICT

ITEM	REQUIRED	PROPOSED
LOT AREA	40,000 S.F.	131,158 SF.
MIN. STREET FRONTAGE	80 FT.	481 FT.
FRONT YARD SETBACK	30 FT.	N/A
SIDE SETBACK	15 FT.	N/A
REAR SETBACK	30 FT.	N/A
BUILDING COVERAGE	NO MAX.	N/A
IMPERVIOUS COVERAGE	NO MAX.	2.14 AC
MAX. BLDG. HEIGHT	NO MAX.	N/A
MIN. BUILDABLE AREA	NO MIN.	N/A
PARKING SPACES	-	61 SPACES

PROPOSED DEVELOPMENT

THE PROPOSED DEVELOPMENT INCLUDES THE CONSTRUCTION OF A STAND ALONE PARKING FACILITY FOR RAND-WHITNEY REALTY. THE DEVELOPMENT WILL INCLUDE ASPHALT DRIVEWAYS AND PARKING AREAS AND ASSOCIATED STORMWATER MANAGEMENT AND WATER QUALITY MEASURES. THE DEVELOPMENT ALSO INCLUDES REPLACEMENT OF AN EXISTING 30" STORM PIPE BELONGING TO THE TOWN OF MONTVILLE. THE PROPOSED DEVELOPMENT WILL DISTURB APPROXIMATELY 3.75 ACRES IN TOTAL AND PERMANENTLY DISTURB 0.16 ACRES (6,753 S.F.) OF MAN-MADE WETLAND.

1. A PORTION OF THE SITE LIES WITHIN A 100-YEAR FLOOD PLAIN. (FIRM MAP #09011C0334G, EFFECTIVE 7/18/2011)
2. NO DIRECT DISTURBANCE TO INLAND WETLANDS IS PROPOSED. PORTIONS OF THE WORK WILL BE PERFORMED WITHIN UPLAND REGULATED AREAS.
3. NO PORTION OF THE LOT LIES WITHIN AN AQUIFER PROTECTION AREA.
4. NO PORTION OF THE SITE LIES WITHIN A WATER SUPPLY PROTECTION AREA.
5. NO PORTION OF THE LOT LIES WITHIN A CT DEEP NATURAL DIVERSITY DATABASE AREA.
6. NO PORTION OF THE LOT LIES WITHIN THE COASTAL RESOURCE MANAGEMENT BOUNDARY.

LEGEND


- FLOOD ZONE AE (FROM FIRM PANEL 09011C0334G 7/18/2011)
- REGULATORY FLOODWAY
- UPLAND REVIEW AREA

APPROVED BY THE MONTVILLE PLANNING AND ZONING COMMISSION

FINAL APPROVAL: _____ DATE: _____

DATE OF APPROVAL: _____

EXPIRATION DATE: _____



CLA Engineers, Inc.
CIVIL • STRUCTURAL • SURVEYING
317 Main Street Norwich, CT 06360
(860) 886-1966 Fax (860) 886-9165


PROJECT NO. CLA-7787F
PROJ. ENGINEER D.P.H.
DATE: 06/02/25
SHEET NO. 4

RAND-WHITNEY REALTY, LLC
PROPOSED TRAILER STORAGE
375 MAPLE AVENUE & ROUTE 163
MONTVILLE, CT
SITE PLAN

STATE OF CONNECTICUT
NO. 24488
LICENSED PROFESSIONAL ENGINEER

REVISION
DATE
NO.

CLA



- LEGEND**
- FLOOD ZONE AE (FROM FIRM PANEL 09011C0334G 7/18/2011)
 - REGULATORY FLOODWAY
 - UPLAND REVIEW AREA

APPROVED BY THE MONTVILLE PLANNING AND ZONING COMMISSION

FINAL APPROVAL: _____ DATE _____

DATE OF APPROVAL: _____

EXPIRATION DATE: _____

CLA Engineers, Inc. CIVIL • STRUCTURAL • SURVEYING 317 Main Street Norwich, CT 06360 (860) 886-1966 Fax (860) 886-9165		Project No. CLA-7767F
RAND-WHITNEY REALTY, LLC		Proj. Engineer D.P.H.
PROPOSED TRAILER STORAGE 375 MAPLE AVENUE & ROUTE 163 MONTVILLE, CT		Date: 06/02/25
GRADING & DRAINAGE PLAN		Sheet No. 5

SEE EROSION & SEDIMENTATION CONTROL AND STORMWATER MANAGEMENT PLAN FOR ADDITIONAL EROSION & SEDIMENTATION CONTROL INFORMATION, BEST MANAGEMENT PRACTICES AND REQUIREMENTS BEFORE AND DURING CONSTRUCTION

INVASIVE PLANT CONTROL

1. AN ECOLOGIST/WETLANDS PROFESSIONAL WILL FLAG WOODY INVASIVES TO BE REMOVED IN THE VICINITY OF BASIN #1 (I.E., BETWEEN THE TOP OF BERM AND ROCKLAND POND) AND WEEDY SPECIES TO BE SPRAYED AT THE TIME OF PLAN IMPLEMENTATION, AND PREFERABLY JUST PRIOR TO ANY EARTHWORK.
2. TARGETED, RATHER THAN BROADCAST HERBICIDE APPLICATION METHODS, SHALL BE USED. FOR SPRING TREATMENT, CUT EARLY IN GROWING SEASON (LATE APRIL TO MID MAY) AND TREAT SMALL RESPROUTS IN EARLY SUMMER USING A LOW VOLUME SPRAYER. IN EARLY FALL USE THE "CUT-AND-PAINT METHOD," APPLYING HERBICIDE TO A RECENTLY CUT STEM (WITHIN 10 MINUTES) ON BROADLEAF INVASIVES. USE A SELECTIVE HERBICIDE LIKE TRICLOPYR (FOUND IN BRUSH-B-GON, GARLON 3A OR 4A, AND OTHER PRODUCTS), RATHER THAN BROAD-SPECTRUM GLYPHOSATE, TO MINIMIZE IMPACTS ON NON-TARGET PLANTS AND SOIL FAUNA. SEE NOTES ON INVASIVE CONTROL.
3. INVASIVE PLANT CONTROL WITHIN THE AREAS OF PLANTINGS BETWEEN BASIN #1 AND THE POND SHALL TAKE PLACE FOR TWO (2) YEARS FOLLOWING THE YEAR OF PLAN IMPLEMENTATION (I.E. YEARS 1 AND 2), FOLLOWING THE PROCEDURES PROMULGATED BY THE CT DEEP'S CONNECTICUT INVASIVE PLANT WORKING GROUP (CIPWG), AND/OR THE NATURE CONSERVANCY.
4. THE ECOLOGIST/WETLANDS PROFESSIONAL WILL PREPARE A ANNUAL REPORT AND PROVIDE IT TO THE COMMISSION BY NOVEMBER 30 OF EACH YEAR.

UTILIZE PROPOSED WATER QUALITY BASIN AS A TEMPORARY SEDIMENT TRAP DURING CONSTRUCTION. SEE TRAP SIZING TABLE THIS SHEET. SEE CONSTRUCTION DETAILS. EXCAVATE BASIN BOTTOM TO ELEVATION 232. (1-FOOT ABOVE PERMANENT BASIN ELEVATION)

INSTALL 4"x4" SEDIMENT MARKER STAKE. MARK ELEVATION 233 TO INDICATE WHEN SEDIMENT REMOVAL WOULD BE REQUIRED

SEE GENERAL NOTE 3 ABOVE FOR PLANTING INFORMATION

PROVIDE TEMPORARY CONSTRUCTION FENCE AROUND THE SEDIMENT TRAP AREA. PROTECT FROM GROUND DISTURBANCE AND COMPACTION DURING CONSTRUCTION. (TYP.)

NO DISTURBANCE PERMITTED BEYOND THE TREE LINE / CLEARING LIMITS (TYP.)

TEMPORARY VEGETATED SWALE TO DIRECT SURFACE RUNOFF TO TEMPORARY SEDIMENT TRAP 1 DURING CONSTRUCTION. ADJUST ELEVATION AND EXACT LOCATION DURING CONSTRUCTION AS FILL IS PLACED AND AS SITE DEVELOPS. (TYP.)

CONSTRUCTION ENTRANCE PROVIDE & MAINTAIN A ±20' x ±50' ANTI-TRACKING CONSTRUCTION EXIT

GENERAL NOTES:

1. PRIOR TO CONSTRUCTION, THE PROPOSED LIMITS OF DISTURBANCE SHALL BE STAKED BY A LICENSED LAND SURVEYOR.
2. INLAND WETLAND BOUNDARIES SHALL BE RE-STAKED IN THE FIELD BY A LICENSED LAND SURVEYOR OR CERTIFIED SOIL SCIENTIST PRIOR TO INSTALLATION OF EROSION AND SEDIMENTATION CONTROL MEASURES.
3. AFTER STABILIZATION OF THE SLOPE BETWEEN BASIN #1 AND ROCKLAND POND, THE FOLLOWING SHRUBS SHALL BE PLANTED ALTERNATELY ALONG THE EDGE OF DISTURBANCE AT AN INTERVAL OF 10-FEET ON CENTER: 10 Highbush Blueberry, 10 Northern Arrowwood Viburnum, 10 Red Chokeberry

INSTALL STANDARD SIZE RIP-RAP APRON PER DETAIL

CLEAR LOT TO LIMITS SHOWN. DO NOT GRUB. ONLY GRUB LOT AFTER PERIMETER EROSION AND SEDIMENTATION CONTROLS AND THE TEMPORARY SEDIMENT TRAPS ARE IN PLACE AND HAVE BEEN APPROVED BY TOWN STAFF.

PROVIDE & MAINTAIN A CONTINUOUS DOUBLE ROW OF SILT FENCE & HAYBALES DURING CONSTRUCTION (TYP.)

OUTLET 36" HDPE FES ELEV. =229.75

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

8' WIDE LEVEL SPREADER (ELEV. 234.0)

SEDIMENT TRAP #1 (BOTT. ELEV. =232.0)

234

236

238

240

242

244

246

248

250

252

254

256

258

260

262

264

266

268

270

272

274

276

278

280

282

284

286

288

290

292

294

296

298

300

302

304

306

308

310

312

314

316

318

320

322

324

326

328

330

332

334

336

338

340

342

344

346

348

350

352

354

356

358

360

362

364

366

368

370

372

374

376

378

380

382

384

386

388

390

392

394

396

398

400

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00

INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

INV IN=(36" SW)=230.00


INV OUT=(36" E)=230.00

46" - 36" CORRUGATED HDPE PIPE S=0.5%

5' DMH TF=235.04

EROSION & SEDIMENTATION CONTROL NARRATIVE

1. THE EROSION & SEDIMENTATION CONTROL PLAN AND DETAILS HAVE BEEN DEVELOPED AS A STRATEGY TO CONTROL SOIL EROSION AND SEDIMENTATION DURING AND AFTER CONSTRUCTION. THIS PLAN IS BASED ON THE "2024 CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL" BY THE CONNECTICUT COUNCIL ON SOIL AND WATER CONSERVATION IN COOPERATION WITH THE CONNECTICUT DEEP.
2. THE PROPOSED LOCATIONS OF SEDIMENT AND EROSION CONTROL MEASURES ARE SHOWN ON THE PLANS. THE CONTRACTOR SHALL PROVIDED SILT FENCE, STONE CHECK DAMS AND/OR OTHER EROSION CONTROL MEASURES AS NEEDED OR DIRECTED BY THE ENGINEER OR TOWN STAFF TO ADEQUATELY PREVENT SEDIMENT TRANSPORT.
3. EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO SITE DISTURBANCE.
4. TOWN STAFF SHALL BE NOTIFIED PRIOR TO THE START OF CONSTRUCTION TO INSPECT SEDIMENTATION AND EROSION CONTROL MEASURES
5. THE CONTRACTOR SHALL INSPECT, REPAIR AND/OR REPLACE EROSION CONTROL MEASURES EVERY 7 DAYS AND IMMEDIATELY FOLLOWING ANY SIGNIFICANT RAINFALL OR SNOW MELT. SEDIMENT DEPOSITS MUST BE REMOVED WHEN WHEN DEPOSITS REACH APPROXIMATELY ONE HALF THE HEIGHT OF THE BARRIER. SEDIMENT CONTROL DEVICES SHALL REMAIN IN PLACE AND BE MAINTAINED BY THE CONTRACTOR UNTIL AREAS UPSLOPE ARE PERMANENTLY STABILIZED.
6. STAKED HAY BAILE SILT BARRIERS AND/OR SILT FENCE SHALL BE INSTALLED AROUND ANY TEMPORARY STOCKPILE AREAS. TEMPORARY VEGETATIVE COVER MAY BE REQUIRED (SEE NOTES).
7. INLET SEDIMENTATION CONTROL DEVICES SHALL BE INSTALLED UNDER THE GRATES OF ALL NEW CATCH BASINS AT THE TIME OF INSTALLATION, AND UNDER THE GRATES OF EXISTING CATCH BASINS IN THE CONSTRUCTION AREA.
8. CONTINUOUS DUST CONTROL USING WATER OR APPROVED EQUAL SHALL BE PROVIDED FOR ALL EARTH STOCKPILES, EARTH PILED ALONG EXCAVATIONS, SURFACES OF BACKFILLED TRENCHES AND GRAVELED ROADWAY SURFACES. **THE USE OF CALCIUM CHLORIDE FOR DUST CONTROL SHALL BE PROHIBITED.**
9. IF DEWATERING IS NECESSARY DURING ANY TIME OF CONSTRUCTION A CLEAR WATER DISCHARGE SHALL BE PROVIDED.
10. ALL DISTURBED AREAS SHALL BE RESTORED PER THE SLOPE STABILIZATION AND PERMANENT VEGETATION DETAILS. ALL DISTURBED AREAS THAT ARE SLOPED LESS THAN THREE HORIZONTAL TO ONE VERTICAL (3:1) SLOPE SHALL BE LOAMED, SEEDED, FERTILIZED AND MULCHED PER THE PERMANENT VEGETATIVE COVER SPECIFICATIONS. EROSION CONTROL MATTING OR STABILIZED HYDROSEED SHALL BE PROVIDED ON ALL DISTURBED AREAS THAT ARE SLOPED MORE THAN THREE HORIZONTAL TO ONE VERTICAL (3:1).
11. IF FINAL SEEDING OF DISTURBED AREAS IS NOT TO BE COMPLETED BEFORE OCTOBER 15, THE CONTRACTOR SHALL PROVIDE TEMPORARY MULCHING (DORMANT SEEDING MAY BE ATTEMPTED AS WELL) TO PROTECT THE SITE AND DELAY PERMANENT SEEDING.
12. WHEN FEASIBLE, TEMPORARY SEEDING OF DISTURBED AREAS THAT HAVE NOT BEEN FINISHED GRADED SHALL BE COMPLETED PRIOR TO OCTOBER 15.
13. ANY EROSION WHICH OCCURS WITHIN THE DISTURBED AREAS SHALL BE IMMEDIATELY REPAIRED AND STABILIZED. DURING THE CONSTRUCTION PHASE, INTERCEPTED SEDIMENT SHALL BE RETURNED TO THE SITE. POST SEEDING, INTERCEPTED SEDIMENT, IF ANY, SHALL BE DISPOSED OF IN A MANNER APPROVED BY THE TOWN AND ENGINEER.
14. EROSION AND SEDIMENTATION CONTROL MEASURES SHALL REMAIN IN PLACE UNTIL VEGETATION IS RE-ESTABLISHED OR SLOPES ARE STABILIZED AND REMOVAL IS APPROVED BY THE TOWN.
15. UNFORESEEN PROBLEMS WHICH ARE ENCOUNTERED IN THE FIELD SHALL BE SOLVED ACCORDING TO THE "2024 CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL" BY THE CONNECTICUT COUNCIL ON SOIL AND WATER CONSERVATION IN COOPERATION WITH THE CONNECTICUT DEEP.
16. THE OWNER'S REPRESENTATIVE SHALL BE RESPONSIBLE FOR THE EROSION AND SEDIMENTATION CONTROLS



INSTALLATION NOTES:

1. PROVIDE 4" THICKNESS OF TOPSOIL OVER CLEAN FILL. PREPARE SOIL BEFORE INSTALLING BLANKETS, INCLUDING APPLICATION OF LIME, FERTILIZER, AND SEED MIX PER PERMANENT VEGETATIVE COVER NOTES. (SHALL BE PAID FOR AT THE UNIT PRICE FOR LOAM, SEED, FERTILIZE & MULCH)
2. BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE BLANKET IN 6" DEEP x 6" WIDE TRENCH, BACKFILL AND COMPACT THE TRENCH AFTER STAPLING.
3. ROLL THE BLANKET (A) DOWN OR (B) HORIZONTALLY ACROSS THE SLOPE.
4. THE EDGES OF PARALLEL BLANKETS MUST BE STAPLED WITH APPROXIMATELY 2" OVERLAP.
5. WHEN BLANKETS MUST BE SPICED DOWN THE SLOPE, PLACE BLANKETS END OVER END (SHINGLE STYLE) WITH APPROXIMATELY 4" OVERLAP. STAPLE THROUGH OVERLAPPED AREA, APPROXIMATELY 12" APART.

PRODUCT NOTES:


1. EROSION CONTROL MATTING MUST BE LISTED ON THE LATEST CT DOT QUALIFIED PRODUCTS LIST UNDER CLASS E SLOPE PROTECTION, TYPE D.

EROSION CONTROL MATTING DETAIL
(FOR 3:1 SLOPES OR STEEPER)

NOTES:

1. HYDROSEED SHALL BE INSTALLED IN ACCORDANCE WITH SECTION 9.50.3.b OF DOT FORM 818.
2. BONDED FIBER MATRIX (BFM) OR FLEXIBLE GROWTH MEDIUM (FGM) MUST BE INCLUDED IN THE HYDROSEED SLURRY. MIX RATE PERCENTAGES SHALL BE IN ACCORDANCE WITH THE MANUFACTURERS RECOMMENDATIONS FOR THE FINISHED SLOPES. THE FOLLOWING ARE ACCEPTABLE PRODUCTS:
- A. PROFILE FLEXITERRA FGM
- B. PROFILE HYDRO-BLANKET BONDED FIBER MATRIX
- C. MAT, INC. SOIL GUARD BONDED FIBER MATRIX
- D. NORTH AMERICAN GREEN HYDRA GT OR HYDRA CM
3. THE REQUIRED SEED MIX SHALL BE IN ACCORDANCE WITH THE PERMANENT VEGETATIVE COVER NOTES. ALL APPLICATION RATES SHALL BE INCREASED BY 10% FOR HYDROSEEDING.
4. THE CONTRACTOR SHALL ENSURE 100% COVERAGE OF THE DISTURBED SOIL

HYDROSEED REQUIREMENTS
(FOR 3:1 SLOPES OR STEEPER)



TYPICAL LOAM & SEED SECTION DETAIL
(FOR ALL DISTURBED AREAS)

SLOPE STABILIZATION DETAILS

NOT TO SCALE

TEMPORARY VEGETATIVE COVER

A TEMPORARY SEEDING OF RYE GRASS WILL BE COMPLETED WITHIN 15 DAYS OF THE FORMATION OF STOCKPILES. IF THE SOIL IN THE STOCKPILES HAS BEEN COMPACTED BY CONSTRUCTION OPERATIONS IT SHALL BE LOOSENED TO A DEPTH OF 2 INCHES BEFORE THE FERTILIZER, LIME AND SEED IS APPLIED. 10-10-10 FERTILIZER AT A RATE OF 7.5 POUNDS PER 1000 S.F. LIMESTONE AT A RATE OF 90 LBS. PER 1000 S.F. SHALL BE USED. RYE GRASS APPLIED AT A RATE OF 1 LB. PER 1000 S.F. SHALL PROVIDE THE TEMPORARY VEGETATIVE COVER. STRAW FREE FROM WEEDS AND COARSE MATTER SHALL BE USED AT A RATE OF 70-90 LBS. PER 1000 S.F. AS A TEMPORARY MULCH. APPLY MULCH AND DRIVE TRACKED EQUIPMENT UP AND DOWN SLOPE OVER ENTIRE SURFACE SO CLEAT MARKS ARE PARALLEL TO THE CONTOURS.

PERMANENT VEGETATIVE COVER

- TOPSOIL WILL BE REPLACED ONCE THE EXCAVATIONS HAVE BEEN COMPLETED AND THE SLOPES ARE GRADED AS SHOWN ON THE PLANS. PROVIDE SLOPE PROTECTION AS CALLED FOR ON THE PLANS AND DETAILS. TOPSOIL SHALL BE SPREAD AT A MINIMUM COMPACTED DEPTH OF 6 INCHES. ONCE THE TOPSOIL HAS BEEN SPREAD, ALL STONES TWO INCHES OR LARGER IN ANY DIMENSION WILL BE REMOVED AS WELL AS DEBRIS.
- APPLY AGRICULTURAL GROUND LIMESTONE AT THE RATE OF TWO TONS PER ACRE OR 100 LBS. PER 1000 S.F.
 - APPLY 10-10-10 FERTILIZER OR EQUIVALENT AT A RATE OF 300 LBS. PER ACRE OR 7.5 LBS. PER 1000 S.F.
 - WORK LIMESTONE AND FERTILIZER INTO THE SOIL TO A DEPTH OF 4 INCHES.
 - INSPECT SEEDBED BEFORE SEEDING.
 - IF TRAFFIC HAS COMPACTED THE SOIL, RETILL COMPACTED AREAS.
 - APPLY THE FOLLOWING GRASS SEED MIX:

TYPICAL SEED MIXTURE

THE NEW ENGLAND ROADSIDE MATRIX UPLAND SEED MIX BY NEW ENGLAND WETLAND PLANTS, INC.

APPLICATION RATE: 35 LBS./ACRE : 1,250 SF/LB. MIX IS DESIGNED FOR USE ALONG ROADS AND HIGHWAYS. THIS MIX CONTAINS NATIVE GRASSES, WILDFLOWERS, AND SHRUBS THAT ARE BLENDED TOGETHER AS A NATIVE MATRIX SEED MIX. IN AREAS THAT RECEIVE FREQUENT MOWING, THE COLD SEASON GRASSES WILL DOMINATE, SUCH AS THOSE AREAS CLOSEST TO THE ROADWAY SHOULDER. IN AREAS FARTHER TO THE ROAD, WHICH MAY BE MOWN ONLY ONCE EACH YEAR, OR IN HARD TO MOW AREAS, SUCH AS AROUND SIGNPOSTS, THE WILDFLOWER COMPONENT WILL BECOME DOMINANT. ALONG CUTS AND SIDE SLOPES WHICH MAY NEVER BE MOWN, THE SHRUB COMPONENT WILL ADD DIVERSITY AND BEAUTY TO THE ROADSIDE PLANTINGS. IT IS A PARTICULARLY APPROPRIATE SEED MIX FOR ROADSIDES, INDUSTRIAL SITES, OR CUT AND FILL SLOPES. THIS MIX MAY BE APPLIED BY HYDROSEEDING, OR BY MECHANICAL SPREADER, ALWAYS APPLY ON A CLEAN, WEED-FREE SEED BED, AFTER SOWING, LIGHTLY RAKE OR ROLL THE SITE TO IMPROVE SEED-TO-SOIL CONTACT. BEST RESULTS ARE OBTAINED WITH A MID-LATE SPRING SEEDING. SUMMER SEEDING WILL BENEFIT FROM A LIGHT MULCHING OF CLEAN, WEED-FREE STRAW TO CONSERVE SOIL MOISTURE.

TYPICAL SEED MIXTURE FOR NON-MOWED SLOPES (3:1 OR STEEPER)

CT DEP SEED MIX NO. 26	LBS./ACRE	LBS./1000 S.F.
SWITCHGRASS (BLACKWELL, SHELTER, CAVE-IN-ROCK)	4.0	0.10
BIG BLUESTEM (NAGRA, KAW)	4.0	0.10
LITTLE BLUESTEM (BLAZE, ALDOUS, CAMPER)	2.0	0.05
SAND LOVEGRASS (NE-27, BEND)	1.5	0.03
BIRD'S-FOOT TREFOIL (EMPIRE VIKING)	2.0	0.05
	13.5	0.33

THE RECOMMENDED SEEDING DATES ARE:

APRIL 1 - JUNE 15 AND AUGUST 15 - OCTOBER 15

IMMEDIATELY FOLLOWING SEEDING, FIRM SEED BED WITH A ROLLER AND MULCH WITH WEED FREE STRAW. IF PERMANENT VEGETATIVE COVER IS HAS NOT BEEN ESTABLISHED BY OCTOBER 15, APPLY A TEMPORARY VEGETATIVE COVER ON THE TOPSOIL.

VEGETATIVE COVER FOR WATER QUALITY BASINS


SEED MIXTURE FOR SETTLING BASINS SHALL BE THE "NEW ENGLAND EROSION CONTROL/RESTORATION MIX FOR MOIST SITES" FROM NEW ENGLAND WETLAND PLANTS, AMHERST, MA, TELEPHONE NO. 413-548-8000

THE BEST RESULTS ARE OBTAINED WITH A SPRING SEEDING. SUMMER AND FALL SEEDING REQUIRE A LIGHT MULCHING OF WEED FREE STRAW TO CONSERVE MOISTURE. LATE FALL AND WINTER DORMANT SEEDING REQUIRE A 10% INCREASE IN THE SEEDING RATE. FERTILIZATION IS NOT REQUIRED UNLESS THE SOILS ARE PARTICULARLY INFERTILE.

RAIN GARDEN SEED MIXTURE

LBS./ACRE	LBS./1000 S.F.
NEW ENGLAND EROSION CONTROL/RESTORATION MIX FOR DETENTION BASINS AND MOIST SITES	35 0.80

SPECIES: Virginia Wild Rye, (Elymus virginicus), Creeping Red Fescue, (Festuca rubra), Little Bluestem, (Schizachyrium scoparium), Big Bluestem, (Andropogon gerardii), Fox Sedge, (Carex vulpinoidea), Switch Grass, (Panicum virgatum), Rough Bentgrass, (Agrostis scabra), New England Aster, (Aster novae-angliae), Boneset, (Eupatorium perfoliatum), Grass Leaved Goldenrod, (Euthamia graminifolia), Green Bulrush, (Scirpus atrovirens), Blue Vervain, (Verbena hastata), Soft Rush, (Juncus effusus), Wool Grass, (Scirpus cyperinus)



CONSTRUCTION NOTES:

1. SILT FENCE FILTER CLOTH TO BE SECURELY FASTENED TO GRADE STAKE WITH STAPLES, 6" ON CENTER.
2. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN ONE ANOTHER THEY SHALL OVERLAP BY 6" AND BE FOLDED.
3. BAILES SHALL BE PLACED IN A ROW WITH ENDS TIGHTLY ABUTTING THE ADJACENT BAILES.

SILT FENCE & HAYBALE DETAIL

NOT TO SCALE

APPROVED BY THE MONTVILLE PLANNING AND ZONING COMMISSION

FINAL APPROVAL: CHAIRMAN SIGNATURE DATE

DATE OF APPROVAL:

EXPIRATION DATE:

STORMWATER MANAGEMENT & POLLUTION PREVENTION PLAN

DURING CONSTRUCTION



1. **POLLUTION PREVENTION TEAM:**
THE CONTRACTOR SHALL BE RESPONSIBLE FOR CARRYING OUT THE PROVISIONS OF THIS PLAN.
2. **SWEEPING:**
PARKING LOTS, SIDEWALKS AND OTHER IMPERVIOUS SURFACES BEYOND THE WORK SITE SHALL BE SWEEPED CLEAN OF SAND, SILT AND LITTER DAILY AT THE END OF THE WORK DAY.
3. **OUTSIDE STORAGE:**
ACCESSORIES OR EQUIPMENT STORED OUTSIDE SHALL BE COVERED OR MAINTAINED TO MINIMIZE POSSIBILITY OF THESE MATERIALS OR THEIR RESIDUE PASSING TO STORM WATER.
4. **WASHING:**
NO WASHING OF VEHICLES, ACCESSORIES, EQUIPMENT, OR APPLIANCES IN WORK SITE.
5. **MAINTENANCE AND INSPECTION:**
A. THE CONTRACTOR SHALL INSPECT, REPAIR AND/OR REPLACE EROSION CONTROL MEASURES EVERY 7 DAYS AND IMMEDIATELY FOLLOWING ANY RAINFALL OF ½" OR MORE, OR SIGNIFICANT SNOW MELT.
B. SEDIMENT DEPOSITS MUST BE REMOVED AND DISPOSED OF WHEN THEY REACH THE FOLLOWING LEVELS:
 - SILT FENCE OR HAY BALES: ONE HALF THE HEIGHT OF THE SILT FENCE OR HAY BAILE BARRIER.
 - INLET SEDIMENT CONTROL DEVICES (SILT SACKS): ONE HALF THE STORAGE VOLUME OF THE DEVICE OR WHEN THE RESTRAINT CORD IS NO LONGER VISIBLE.
 - STONE CHECK DAMS AT INLETS: ONE HALF OF THE TEMPORARY SEDIMENT POOL HEIGHT.C. DAILY DUST CONTROL USING WATER OR APPROVED EQUAL SHALL BE PROVIDED FOR ALL EARTH STOCKPILES, EARTH PILED ALONG EXCAVATIONS, SURFACES OF BACKFILLED TRENCHES AND GRAVELED SURFACES.
D. SILT FENCE AND INLET SEDIMENT CONTROL DEVICES SHALL BE REPLACED WITH RIPS OR DETERIORATION IN THE GEOTEXTILE FABRIC ARE FOUND ON INSPECTION. HAY BALES SHALL BE REPLACED IF THEY HAVE DETERIORATED OR DECOMPOSED TO THE POINT WHERE THEY HAVE LOST STRUCTURAL INTEGRITY. CRUSHED STONE SHALL BE REMOVED AND REPLACED IF SILT HAS ACCUMULATED WITH THE STONE VOIDS TO PREVENT THE PASSAGE OF WATER THROUGH THE STONE.
6. **SPILLS OR ACCIDENTAL DISCHARGES:**
A. COMPLY WITH STATE AND FEDERAL REGULATIONS TO CONTAIN AND CLEAN UP ANY SPILL OR DISCHARGE AND DISPOSE OF MATERIALS AT AN APPROVED FACILITY.
B. CONTACT CONNECTICUT DEEP OIL AND CHEMICAL SPILL RESPONSE DIVISION (860) 424-3338
C. THE FOLLOWING STEPS SHOULD BE PERFORMED AS SOON AS POSSIBLE:
 - STOP THE SOURCE OF THE SPILL
 - CONTAIN THE SPILL
 - COVER SPILL WITH ABSORBENT MATERIAL SUCH AS KITTY LITER, SAWDUST OR OIL ABSORBENT PADS. DO NOT USE STRAW.
 - DISPOSE OF ABSORBER IN ACCORDANCE WITH LOCAL AND STATE REGULATIONS.

POST CONSTRUCTION

1. **POLLUTION PREVENTION TEAM:**
THE OWNERS SHALL BE RESPONSIBLE FOR CARRYING OUT THE PROVISIONS OF THIS PLAN.
2. **SWEEPING:**
PARKING LOTS, SIDEWALKS AND OTHER IMPERVIOUS SURFACES SHALL BE SWEEPED CLEAN OF SAND AND LITTER AND ANY OTHER POLLUTANTS AT LEAST TWICE PER YEAR.
A. BETWEEN NOVEMBER 15 AND DECEMBER 15 (AFTER LEAF FALL)
B. DURING APRIL (AFTER SNOW MELT)
3. **OUTSIDE STORAGE:**
ACCESSORIES OR EQUIPMENT STORED OUTSIDE SHALL BE COVERED OR MAINTAINED TO MINIMIZE POSSIBILITY OF THESE MATERIALS OR THEIR RESIDUE PASSING TO STORM WATER.
4. **WASHING:**
NO WASHING OF VEHICLES, ACCESSORIES, EQUIPMENT OR APPLIANCES IN PARKING AREAS.
5. **MAINTENANCE AND INSPECTION:**
SEE OPERATIONS AND MAINTENANCE SCHEDULE
6. **SPILLS OR ACCIDENTAL DISCHARGES:**
A. COMPLY WITH STATE AND FEDERAL REGULATIONS TO CONTAIN AND CLEAN UP ANY SPILL OR DISCHARGE AND DISPOSE OF MATERIALS AT AN APPROVED FACILITY.
B. CONTACT CONNECTICUT DEEP OIL AND CHEMICAL SPILL RESPONSE DIVISION (860) 424-3338
C. THE FOLLOWING STEPS SHOULD BE PERFORMED AS SOON AS POSSIBLE:
 - STOP THE SOURCE OF THE SPILL
 - CONTAIN THE SPILL
 - COVER SPILL WITH ABSORBENT MATERIAL SUCH AS KITTY LITER, SAWDUST OR OIL ABSORBENT PADS. DO NOT USE STRAW.
 - DISPOSE OF ABSORBER IN ACCORDANCE WITH LOCAL AND STATE REGULATIONS.

NOTE: THE CONTRACTOR SHALL CONTINUALLY STORE THE FOLLOWING MATERIALS ONSITE DURING CONSTRUCTION TO MEET UNEXPECTED EROSION NEEDS

- 100 LF OF SILT FENCE
- 10 HAY BALES
- 10 CY OF WOOD CHIPS OR CRUSHED STONE



NOTE:

TO BE PROVIDED IN ALL NEW CATCH BASINS AT THE TIME OF INSTALLATION AND WITHIN BASINS ADJACENT TO THE WORK AREA PRIOR TO THE START OF CONSTRUCTION

INLET SEDIMENT CONTROL DEVICE DETAIL





NOT TO SCALE

Maintenance Schedule for Trailer Storage Areas	
Activity	Schedule
Sweep parking lots & impervious areas	<ul style="list-style-type: none">• Between November 15th and December 15th (after leaf fall)• During April (after snow melt)
Remove and dispose of trash and debris onsite	Daily - As needed maintenance




Maintenance Schedule for Qualifying Pervious Area (QPA)	
Activity	Schedule
Sweep impervious areas	<ul style="list-style-type: none">• Between November 15th and December 15th (after leaf fall)• During April (after snow melt)
Inspect QPA for erosion and loss of vegetation	Annually - As needed maintenance
Remove and dispose of trash and debris onsite	Annually - As needed maintenance

Maintenance Schedule for Stormwater Basins	
Activity	Schedule
Prior to new spring growth reaching a height of 2" (e.g., shortly after forsythia or redbud blooms), trim any material standing from the previous year close to the ground (approximately 2"). This will allow the soil to warm more quickly, which will stimulate the emergence and growth of native seedlings and reduce the likelihood of the meadow being invaded by shrubs. Problem weeds should be hand pulled or spot sprayed with an approved herbicide, such as Rodeo® or Garlon® 3A. If you did not plant vines or spiny plants as part of your mix, be vigilant about controlling them. These are more easily pulled when they are young rather than after they have had two to three months of growth. Examples include bindweed, blackberry, multiflora rose, mile-a-minute and Japanese hops. Be equally vigilant about controlling other invasive species, such as autumn olive and Japanese knotweed. Special Circumstances If you notice a heavy infestation of ragweed or foxtail in the second growing season, trim the meadow to a height of 8". Trimming should cease by mid-September.	Second growing season
For the basin and side slopes, inspect for invasive vegetation. Grassy weeds or persistent perennials can re-establish in these soils. Monitor and control weeds by hand pulling or spot spraying.	Monthly
Inspect for damage, undercut, or eroded area Inspect Sediment Forebay and monitor for sediment accumulation. Remove any trash and organic debris (leaves) in spring & fall. Remove sediment from the sediment forebay or other pretreatment area when it accumulates to a depth of more than 12 inches or 50% of the design depth. Clean outlet of sediment forebay or other pretreatment measures when drawdown time exceeds 36 hours after the end of a storm event. Remove sediment from the infiltration basin surface when the sediment accumulation exceeds 2 inches or when drawdown time exceeds 48 hours after the end of a storm event, indicating that the system is clogged. Weed as necessary. Mow grass within infiltration basin to a height of 3 to 6 inches. Maintain a healthy, vigorous stand of grass cover; re-seed as necessary. Clean and remove debris & sediment from inlet and outlet structures. Mow side slopes. Close mowing throughout the regular growing season or extensive chemical use is not conducive to water quality improvement and wildlife habitat. Spring mowed vegetation can typically remain within basins providing cover for new emerging vegetation. Repair undercut or eroded areas.	Semi-Annually
	As needed maintenance



		CLA Engineers, Inc. CIVIL • STRUCTURAL • SURVEYING 317 Main Street Norwich, CT 06360 (860) 886-1966 Fax (860) 886-9165	
No.	DATE	REVISION	
		RAND-WHITNEY REALTY, LLC	
		PROPOSED TRAILER STORAGE 375 MAPLE AVENUE & ROUTE 163 MONTVILLE, CT	
		E&S NOTES & DETAILS	
		Project No. CLA-7767F	
		Proj. Engineer D.P.H.	
		Date: 06/02/25	
		Sheet No. 7	



NOTES:
1. CONTRACTOR SHALL PROTECT EXCAVATIONS BY SHORING, BRACING, SHEET PILING, UNDERPINNING OR OTHER METHODS TO PREVENT CAVE-IN OR LOOSE SOIL FROM FALLING INTO THE EXCAVATION AND DAMAGING THE WORK OR ADJACENT STRUCTURES AND UTILITIES.




STORMWATER QUALITY BASIN EMBANKMENT FILL SECTION DETAIL
NOT TO SCALE



CULVERT END PLAN VIEW
TYPE A - RIPRAP APRON
NOT TO SCALE



Type A (STANDARD SIZE RIP-RAP)

Q=	71	cfs
Sp=	2.5	feet
La=	40.1	feet
W1=	7.5	feet
W2=	35.5	feet







- NOTES:
1. PERVIOUS TOPSOIL MIX SHALL MEET THE REQUIREMENTS OF DOT FORM 818, ARTICLE M.13.01.1 WITH THE FOLLOWING GRADATION:
SIEVE % PASSING
#10 100%
#40 60-80%
#80 5%
#200 0%
DO NOT COMPACT MATERIAL DURING INSTALLATION.
2. FINE SAND SHALL MEET THE FOLLOWING GRADATION:
Sieve % Passing
No. 20 100%
No. 40 100%
No. 60 100%
No. 100 50-75%
No. 140 0%
3. EXCAVATE WATER QUALITY BASIN TO THE GRADES SPECIFIED WITH SIDEWALLS AS NEAR TO VERTICAL AS POSSIBLE. INSTALL PERVIOUS TOPSOIL MIX. DO NOT COMPACT TOPSOIL MIX.
4. SEED MIX SHALL CONFORM TO THE REQUIREMENTS SPECIFIED IN THE VEGETATIVE COVER NARRATIVE HEREIN.
5. INSTALL SHRUBS AND ALL PLANTINGS IN CONFORMANCE WITH THE CONSTRUCTION DETAILS AND LANDSCAPING NOTES HEREIN.
MAINTENANCE:
1. MOW BOTTOM 2-3 TIMES PER YEARS, AS NEEDED.
2. REPLENISH MULCH AROUND PLANTINGS AS NEEDED.
3. REMOVE SEDIMENT AND LEAF LITTER TWICE YEARLY
A. BETWEEN NOVEMBER 15 AND DECEMBER 15 (AFTER LEAF FALL)
B. DURING APRIL (AFTER SNOW MELT)

TYPICAL STORMWATER QUALITY BASIN DETAILS
NOT TO SCALE



APPROVED BY THE LISBON PLANNING AND ZONING COMMISSION
FINAL APPROVAL: _____ DATE _____
DATE OF APPROVAL: _____
EXPIRATION DATE: _____



- NOTES:
1. INSTALLATION OF RAIL AND ANCHORAGES TO BE IN ACCORDANCE WITH THE REQUIREMENTS OF CT DOT.
2. METAL BEAM RAIL TO BE DOT TYPE RB-350 PER DOT SPECIFICATIONS.
3. PROVIDE RB-TYPE II END ANCHORAGES PER DOT SPECIFICATIONS.

METAL BEAM RAIL AND END ANCHORAGE
NOT TO SCALE

CLA Engineers, Inc. CIVIL • STRUCTURAL • SURVEYING 317 Main Street Norwich, CT 06360 (860) 886-1966 Fax (860) 886-9165		Project No. CLA-7787F Proj. Engineer D.P.H. Date: 06/02/25 Sheet No. 8
RAND-WHITNEY REALTY, LLC 375 MAPLE AVENUE & ROUTE 163 MONTVILLE, CT CONSTRUCTION DETAILS		No. DATE REVISION